



FOR REGISTRY USE ONLY

I, CAROL FALVEY, CLERK OF THE TOWN OF HINGHAM, HEREBY CERTIFY THAT THE NOTICE OF APPROVAL OF THIS PLAN BY THE PLANNING BOARD HAS BEEN RECEIVED AND RECORDED AT THIS OFFICE AND NO NOTICE OF APPEAL WAS RECEIVED DURING THE TWENTY DAYS NEXT FOLLOWING SUCH RECEIPT AND RECORDING OF SAID NOTICE.

DATE \_\_\_\_\_ TOWN CLERK \_\_\_\_\_  
 APPROVED \_\_\_\_\_ SUBJECT TO COVENANT CONDITIONS SET FORTH IN A COVENANT EXECUTED BY \_\_\_\_\_ DATED \_\_\_\_\_, AND TO BE RECORDED HERewith.

APPROVAL UNDER SUBDIVISION CONTROL LAW IS REQUIRED  
 DATE SUBMITTED: \_\_\_\_\_  
 DATE APPROVED: \_\_\_\_\_  
 DATE ENDORSED: \_\_\_\_\_

HINGHAM PLANNING BOARD  
 DATE SUBMITTED: \_\_\_\_\_  
 DATE APPROVED: \_\_\_\_\_  
 DATE ENDORSED: \_\_\_\_\_

HINGHAM BOARD OF HEALTH  
 I DO HEREBY CERTIFY THAT THE SUBDIVISION AS SHOWN HEREON CONFORMS WITH THE TOWN OF HINGHAM PLANNING BOARD SUBDIVISION RULES & REGULATIONS EXCEPT FOR THE WAIVERS AS REQUESTED.

KEVIN S. GRADY  
 CIVIL  
 No. 46264  
 PROFESSIONAL ENGINEER

11/17/21  
 DATE

I HEREBY CERTIFY THAT THIS PLAN HAS BEEN PREPARED IN CONFORMANCE WITH THE RULES AND REGULATIONS OF THE REGISTERS OF DEEDS OF THE COMMONWEALTH OF MASSACHUSETTS.

TIMOTHY R. BENNETT  
 P.L.S. #36856  
 PROFESSIONAL LAND SURVEYOR

11/17/21  
 DATE

## DRAINAGE DEFINITIVE SUBDIVISION PLAN

### #101 GARDNER STREET HINGHAM, MASSACHUSETTS

PREPARED FOR:  
 Ms. CHRISTINE WALKER, CONTROLLER  
 BOSTON GOLF CLUB  
 #19 OLD COUNTY ROAD  
 HINGHAM, MA 02043

FEBRUARY 26, 2021  
 SCALE: AS SHOWN  
 JOB No. 20-164

**GRADY CONSULTING, L.L.C.**  
 Civil Engineers, Land Surveyors & Landscape Architects  
 71 Evergreen Street, Suite 1, Kingston, MA 02364  
 Phone (781) 585-2300 Fax (781) 585-2378

### EROSION & SEDIMENT CONTROL PLAN

THE LONG TERM OPERATION AND MAINTENANCE PLAN (O & M PLAN) ATTACHED TO THE STORM WATER DRAINAGE CALCULATIONS INCLUDES ADDITIONAL MEASURES REQUIRED BY THE STANDARD 4 OF THE MASSACHUSETTS STORM WATER HANDBOOK VOLUME 1 CHAPTER 1.

- ADDITIONAL REQUIREMENTS**
- GOOD HOUSE KEEPING
  - STORING MATERIALS AND WASTE PRODUCTS - FUEL SHALL BE STORED OFF SITE, MATERIAL STOCKPILE SHALL BE AS INDICATED ON PLAN FOR SOIL.
  - VEHICLE WASHING - SHALL BE CONDUCTED OFF SITE
  - ROUTINE INSPECTIONS - SHALL BE DONE AS INDICATED ON THE O & M PLAN. STORAGE AND USE OF FERTILIZERS AND PESTICIDES - SEE O & M PLAN
  - PROPER MANAGEMENT OF DEBRIS MATERIALS AND SNOW STORAGE - SEE O & M PLAN

THE CONTRACTOR SHALL INSTALL SILT FENCE EROSION CONTROL AS SHOWN ON THIS PLAN. THE SILT FENCE EROSION CONTROL INDICATES THE LIMIT OF CLEARING AND LIMIT OF WORK FOR THE PROJECT.

CONSTRUCTION ENTRANCES SHALL BE INSTALLED AND CONSTRUCTED AS DETAILED.

STOCKPILES SHALL BE SURROUNDED BY SILT FENCE BARRIER ON THE DOWN GRADIENT SIDE TO MITIGATE SEDIMENTATION.

SILT SACKS SHALL BE INSTALLED IN CATCH BASINS AND SHALL REMAIN IN PLACE UNTIL SITE STABILIZATION HAS OCCURRED.

### REQUIRED INSPECTIONS

THE DEPARTMENT OR ITS AGENT SHALL PERFORM INSPECTIONS AS LISTED BELOW, AND SHALL EITHER APPROVE THAT PORTION OF THE WORK COMPLETED OR SHALL NOTIFY THE PERMITTEE OF ANY NONCOMPLIANCE WITH PERMIT REQUIREMENTS. IN ORDER TO OBTAIN INSPECTIONS, THE PERMITTEE SHALL NOTIFY THE DEPARTMENT AT LEAST TWO BUSINESS DAYS PRIOR TO THE REQUESTED INSPECTION. INSPECTIONS SHALL OCCUR AT THE FOLLOWING STAGES:

- 1) EROSION AND SEDIMENT CONTROL MEASURES ARE IN PLACE AND STABILIZED
- 2) SITE CLEARING HAS BEEN SUBSTANTIALLY COMPLETED
- 3) STORMWATER MANAGEMENT SYSTEM
  - i) ROUGH GRADING HAS BEEN SUBSTANTIALLY COMPLETED
  - ii) FINAL GRADING HAS BEEN SUBSTANTIALLY COMPLETED
  - iii) FINAL LANDSCAPING (PERMANENT STABILIZATION) AND PROJECT FINAL COMPLETION

REVISIONS	PLANNING/BOH REVIEW COMMENTS
4/22/21	PLANNING/BOH REVIEW COMMENTS
4/29/21	PLANNING/BOH REVIEW COMMENTS
6/28/21	PLANNING/BOH REVIEW COMMENTS
8/12/21	PLANNING BOARD COMMENTS

**NEW ENGLAND WETLAND PLANTS, INC.**  
 820 WEST STREET, AMHERST, MA 01002  
 PHONE: 413-548-8000 FAX 413-548-4000  
 EMAIL: INFO@NEWPLANTS.COM WEB ADDRESS: WWW.NEWPLANTS.COM

**New England Conservation/Wildlife Mix**

Botanical Name	Common Name	Indicator
<i>Elymus virginicus</i>	Virginia Wild Rye	FACW
<i>Schizanthus scogorium</i>	Little Bluestem	FACU
<i>Andropogon gerardii</i>	Big Bluestem	FAC
<i>Festuca rubra</i>	Red Fescue	FACU
<i>Scoropachya nutans</i>	Indian Grass	UPL
<i>Panicum virgatum</i>	Switch Grass	FAC
<i>Chamaecrista fasciculata</i>	Partridge Pea	FACU
<i>Desmodium canadense</i>	Shovely Tick Trefoil	FAC
<i>Astilbe tuberosa</i>	Butterfly Milkweed	NI
<i>Hibiscus frondosa</i>	Beggar Ticks	FACW
<i>Eupatorium purpureum (Eupatorium maculatum)</i>	Purple Joe Pye Weed	FAC
<i>Rudbeckia hirta</i>	Black Eyed Susan	FACU
<i>Aster pilosus (Symphyotricum pilosum)</i>	Heath (or Hair) Aster	UPL
<i>Solidago juncea</i>	Early Goldenrod	

PRICE PER LB. \$39.50 MIN. QUANTITY 2 LBS. TOTAL: \$79.00 APPLY 25 LBS/ACRE 1750 sq ft/AC

The New England Conservation/Wildlife Mix provides a permanent cover of grasses, wildflowers, and legumes for both good erosion control and wildlife habitat value. The mix is designed to be a no maintenance seeding, and is appropriate for cut and fill slopes, detention basin side slopes, and disturbed areas adjacent to commercial and residential projects.

New England Wetland Plants, Inc. may modify seed mixes at any time depending upon seed availability. The design criteria and ecological function of the mix will remain unchanged. Prices in bulk pound, PDS warehouse, Flat SH and applicable taxes.

